



무대장치 천정평면 배치도
S : 1 / 100

-LIST-

NO.	SPECIFICATION	DIMENSION	Q'TY	REMARK	NO.	SPECIFICATION	DIMENSION	Q'TY	REMARK
1	PLACARD BATTEN	14,800L , 1.5KW x 4P	1 SET	UP/DN	13	FLAG BATTEN	14,800L , 1.5KW x 4P	1 SET	UP/DN
2	CONTOUR CURTAIN	18,000Wx11,000H / 0.75KWx4Px3SET	1 SET	3 번형	14	HEAD CURTAIN	17,200W x 1,500H	1 SET	
3	NO.1 BODER LIGHT BATTEN	14,800L , 2.2KW x 6P	1 SET	UP/DN	15	SCREEN COVER CURTAIN	17,200W x 10,000H, 0.4W x 4P	1 SET	OP/CL
4	NO.1 SUSPENSION LIGHT BATTEN	14,800L , 2.2KW x 6P	1 SET	UP/DN	16	CEILING LIGHT BATTEN	14,800L , 2.2KW x 6P	1 SET	UP/DN
5	NO.1 SIDE CURTIAN	2,500W x 10,500H	2 SET	MANUAL TYPE	19	FOLLOW SPOT LIGHT	MSR 1.2KW	1 SET	
6	NO.2 BODER LIGHT BATTEN	14,800L , 2.2KW x 6P	1 SET	UP/DN	20	DIMMER & MOTOR CONTROL PANEL	DIM 66, RD 12, MOTOR 15	2 번	
7	NO.2 SUSPENSION LIGHT BATTEN	14,800L , 2.2KW x 6P	1 SET	UP/DN	21	COMPUTER CONSOLE	48/96 CH	1 SET	
8	SET BATTEN	14,800L , 1.5KW x 4P	1 SET	UP/DN		SUB CONTROL CONSOLE	1M 10CH ¹ , RD 12, MOTOR 15	1 SET	
9	DRAW CURTIAN	18,600W x 10,500H / 0.4KW x 4P	1 SET	OP/CL		CONNECTOR BOX		1 SET	
10	NO.3 SUSPENSION LIGHT BATTEN	14,800L , 2.2KW x 6P	1 SET	UP/DN					
11	UPPER LIGHT BATTEN	14,800L , 2.2KW x 6P	1 SET	UP/DN					
12	NO.2 SIDE CURTIAN	2,500W x 10,500H	2 SETS	MANUAL TYPE					

NOTE

NO.	DESCRIPTION	DATE	BY	APPR.

REVISIONS



ARCHITECTURE PLANNING ENGINEERING
(주)코어플래닝엔지니어링사무소
TEL. (02)562-0788, FAX. (02)562-0728

PROJECT TITLE 새명당

부천시 오정구청사 신축공사

NAME OF DRAWING 도명

문화선라 무대장치
천정평면 배치도

DATE 2002. 12. DESIGNED BY 김기

SCALE 1 / 100 CHECKED BY 김기

DRAWN BY 김기 APPROVED BY 김기

DRAWING NO. 도명번호

E - 105

FILE NAME SHEET NO. 시트번호

PROJECT NUMBER 00TA004